Taylor Apartments
Building No. 4 Office Design
Troy, New York

Owner: TroyHousing Authority
Total Construction Cost: $168,370.00

Renovate entire floor, consisting of seven apartments, to office space. Provide required modifications to the existing heating system to accommodate wall removals. Provide demolition drawings for the removal of toilet rooms. Provide new handicapped accessible toilet room design.

Electrical work involved revising the existing electrical distribution system on the first floor to consolidate seven separately metered apartment panels to one house meter. Provide additional panelboards and feeders to completely air condition the first floor offices. Provide complete new lighting, receptacles, voice/data outlets and empty raceways. Provide complete security and intrusion alarm system, closed circuit TV system with monitors and VCR playback feature.

PLUMB ENGINEERING, P.C.
4 Wolfert Avenue, Albany, New York 12204 Phone: 518-465-6037 Fax: 518-465-5210 E-Mail: Engineers@Plumbpc.com